

General

Rig Name	EDC Rig 1K
Rig Category	WorkOver
Rig Type	Mast Trailer - Telescoping Rig
Rig HP	750 HP
Year Built	2021
Manufacturer	Hong Hua (HH)
Rated Drilling Depth	9843 FT
Rig Move Loads	66

Drilling Equipment

Mast height	114.3 FT
Hook Load	180 TON
Setback Load	90.7 TON
Rotary Table	Hong Hua (HH) - ZP205RT - Maximum Diameter 20 1/2 INCH
Drawworks	Hong Hua (HH) - JC30DB Drawworks
Drilling Line	1 1/8 INCH
Top Drive / Kelly	Kelly National Oil Well Varco KS6600
Mud Pumps	HHF-800

Power Supply Equipment

Main Power Supply	5 EA CATERPILLAR C-15 Diesel Engines
Emergency Power Supply	2 EA CATERPILLAR C-07 Diesel Engines

Well Control Equipment

Annular Ram	13 5/8 INCH X 5,000 PSI WP
Pipe Ram	13 5/8 INCH X 5,000 PSI WP
Shear Ram	13 5/8 INCH X 5,000 PSI WP
Choke Manifold	3 1/8 INCH X 5,000 PSI WP
Kill Manifold	2 1/16 INCH X 5,000 PSI WP
Accumulator Unit	4 Station - 3000 PSI WP - 24 x 15 Gallon Bottles

Down Hole Equipment

Drill Pipes	3 1/2 INCH - 2 7/8 INCH
Drill Collars	3 1/8 INCH - 4 3/4 INCH

Storage Facilities

Liquid Mud	1,200 BBLS
Drill water	1,509 BBLS

	Rig Site	Main Camp
Fuel	411 BBLS	165 BBLS
Fresh Water	94.3 BBLS	200 BBLS

Camp Capacity	79 Persons
---------------	------------

