

General

| | |
|----------------------|----------------------|
| Rig Name | EDC Rig 49 |
| Rig Category | Drilling |
| Rig Type | Self Elevating |
| Rig HP | 1,500 |
| Year Built | 1976 - Upgraded 2002 |
| Manufacturer | DRECO |
| Rated Drilling Depth | 15,000 FT |
| Rig Move Loads | 85 |

Drilling Equipment

| | |
|-------------------|---------------------------------|
| Mast height | 142 FT |
| Hook Load | 500 TON |
| Setback Load | 350 TON |
| Rotary Table | OILWELL 27 1/2 INCH |
| Drawworks | NATIONAL 110 UE |
| Drilling Line | 1 3/8 INCH |
| Top Drive / Kelly | BENITEC TD-500XT |
| Mud Pumps | 2 EA NATIONAL OIL WELL 12-P-160 |

Power Supply Equipment

| | |
|------------------------|--------------------------------------|
| Main Power Supply | 3 EA CATERPILLAR 3512 Diesel Engines |
| Emergency Power Supply | N/A |

Well Control Equipment

| | |
|------------------------|-----------------------------|
| Annular BOP | 13 5/8 INCH X 5,000 PSI WP |
| Single BOP | 13 5/8 INCH X 10,000 PSI WP |
| Double BOP | 13 5/8 INCH X 10,000 PSI WP |
| Choke & Kill Manifolds | 4 1/16 INCH X 10,000 PSI WP |
| Accumulator Unit | 3000 PSI WP |

Down Hole Equipment

| | |
|---------------|--------------------------------------|
| Drill Pipes | 5 INCH |
| Drill Collars | 6 1/2 INCH - 8 1/4 INCH - 9 1/2 INCH |

Storage Facilities

| | |
|-------------|------------|
| Liquid Mud | 2,640 BBLS |
| Drill water | 500 BBLS |

| | |
|-------------|----------|
| Fuel | 125 BBLS |
| Fresh Water | 250 BBLS |

Rig Site

| |
|----------|
| 125 BBLS |
| 250 BBLS |

Main Camp

| |
|----------|
| 250 BBLS |
| 500 BBLS |

Camp Capacity

| |
|------------|
| 72 Persons |
|------------|

