

General

| | |
|----------------------|----------------|
| Rig Name | EDC Rig 76 |
| Rig Category | Drilling |
| Rig Type | Self Elevating |
| Rig HP | 2,000 |
| Year Built | 2023 |
| Manufacturer | EPHH |
| Rated Drilling Depth | 20,000 FT |
| Rig Move Loads | 155 |

Drilling Equipment

| | |
|-------------------|---|
| Mast height | 157 FT |
| Hook Load | 1,000000 lbs |
| Setback Load | 800,000 |
| Rotary Table | 37 1/2" HH ZP375 Static load 1,300,000 |
| Drawworks | HH JC70DP |
| Drilling Line | 1 1/2 INCH |
| Top Drive / Kelly | BPM DQ70BSE 500 TON 1200 HP |
| Mud Pumps | AMERICAN BLOCK K- 1600 |

Power Supply Equipment

| | |
|------------------------|--------------------------------------|
| Main Power Supply | 3 EA CATERPILLAR 3512 Diesel Engines |
| Emergency Power Supply | GENLITEC , GPC150S |

Well Control Equipment

| | |
|------------------------|--------------------------------------|
| Annular BOP | 13 5/8 INCH X 5,000 PSI WP |
| Single BOP | 13 5/8 INCH X 10,000 PSI WP |
| Double BOP | 13 5/8 INCH X 10,000 PSI WP |
| Choke & Kill Manifolds | 4 1/16 INCH X 10,000 PSI WP |
| Accumulator Unit | 3000 PSI WP -Accum V 480 gal. 15* 32 |

Down Hole Equipment

| | |
|---------------|--------------------------------------|
| Drill Pipes | 5 INCH |
| Drill Collars | 6 1/2 INCH - 8 1/4 INCH - 9 1/2 INCH |

Storage Facilities

| | |
|-------------|-----------|
| Liquid Mud | 2600 BBLS |
| Drill water | 1500 BBLS |

| | | |
|-------------|-----------------|------------------|
| | Rig Site | Main Camp |
| Fuel | 850 BBLS | 200 BBLS |
| Fresh Water | 200 BBLS | 320 BBLS |

| | |
|----------------------|-----|
| Camp Capacity | 110 |
|----------------------|-----|

