| General<br>Rig Name<br>Rig Category<br>Rig Type<br>Rig HP<br>Year Built<br>Manufacturer<br>Rated Drilling Depth<br>Rig Move Loads              | EDC Rig 34<br>Work Over<br>Platform Rig<br>2000<br>N/A<br>IDECO<br>20,000 FT<br>N/A  |   |
|--|--|---|
| Drilling Equipment<br>Mast height<br>Hook Load<br>Setback Load<br>Rotary Table<br>Drawworks<br>Drilling Line<br>Top Drive / Kelly<br>Mud Pumps | 142 FT<br>550 TON<br>300 TON<br>IDECO 27 1/2 INCH<br>IDECO E2100<br>1 3/8 INCH<br>Kelly<br>2 EA IDECO T-1600, 18   | ننتركة الحفر المصرية<br>EGYPTIAN DRILLING COMPANY |
| Power Supply Equipment<br>Main Power Supply<br>Emergency Power Supply  | 3 EA CAT Diesel D399, 600V AC<br>N/A   |   |
| Well Control Equipment<br>Annular BOP<br>Single BOP<br>Double BOP<br>Choke & Kill Manifolds<br>Accumulator Unit                                | FH35-35, 13 5/8 , 5k<br>13 5/8" INCH x 5,000 PSI WP<br>13 5/8" INCH x 5,000 PSI WP<br>5,000 PSI WP<br>2 Stations - 3,000 PSI WP - 23 x 11 Gallon Bottles |   |
| Down Hole Equipment<br>Drill Pipes<br>Drill Collars  | 3 1/2 INCH<br>4 3/4 INCH   |   |
| Storage Facilities<br>Liquid Mud<br>Drill water  | 1,437 BBLS<br>830 BBLS   |   |
| Fuel<br>Fresh Water  | Rig Site<br>830 BBLS<br>335 BBLS   | Main Camp<br>N/A<br>N/A                           |
| Camp Capacity  | 58 persons   |   |